

ADDENDUM NUMBER 1

Peoria Park District
Planning, Design and Construction Department
1314 N. Park Road
Peoria, Illinois 61604
Telephone (309) 686- 3386

PROJECT TITLE:
Natatorium HVAC Replacement
RiverPlex Recreation and
Wellness Center
600 N.E. Water St.
Peoria, Illinois 61603
PPD Project # 19-023
Dated Feb 23, 2021

ISSUANCE DATE: March 3, 2021

LOCATION: **RiverPlex Recreation and Wellness Center**

The proposed Contract Documents for this Work are modified as follows:

I. PROJECT MANUAL / SPECIFICATIONS/GENERAL CONDITIONS/ETC:

- A. Supplementary Instructions to Bidders. 12. CONSTRUCTION TIME AND LIQUIDATED DAMAGES CLAUSE: PROJECT COMPLETION, 2): Replace "Actual on-site work not affecting the use of the pool area will be permitted to begin on July 1, 2021. Owner will drain pools on August 1, 2021. On-site work in the pool area will be permitted starting August 2, 2021." with "Actual on-site work not affecting the use of the pool area or other patrons, will be permitted to begin after award of the contract. Owner will drain pools on August 1, 2021. On-site work in the pool area will be permitted starting August 2, 2021."
- B. Sample Agreement Between Owner and Contractor, V. DATES OF COMMENCEMENT AND COMPLETION OF THE WORK., B. SUBSTANTIAL COMPLETION: Replace "Actual on-site work not affecting the use of the pool area will be permitted to begin on July 1, 2021. Owner will drain pools on August 1, 2021. On-site work in the pool area will be permitted starting August 2, 2021." with "Actual on-site work not affecting the use of the pool area or other patrons, will be permitted to begin after award of the contract. Owner will drain pools on August 1, 2021. On-site work in the pool area will be permitted starting August 2, 2021."

II. DRAWINGS:

- A. Drawing H101 Add General Note 9. THE UNDERSIDE OF THE ROOF DECK AND THE SUPPORT STEEL IN THE EQUIPMENT ROOM AND ABOVE LAY-IN CEILINGS IS COATED WITH "CAFECO 800" AND "CAFECO BLAZE-SHIELD II" SPRAYED ON FIRE-PROTECTION MATERIAL. WHERE EXISTING UPPER PIPE HANGER ATTACHMENTS CANNOT BE USED OR NEED TO BE SUPPLEMENTED, MINIMALLY REMOVE EXISTING FIRE-PROTECTION MATERIAL FROM THE EXISTING STRUCTURAL STEEL TO ACCOMMODATE THE INSTALLATION OF UPPER ATTACHMENTS. USE "CAFECO FIBER-PATCH/ISOLATEK TYPE P" TO REPAIR THE COATING REMOVED. COAT TO THE SAME DEPTH AS THE EXISTING ADJOINING MATERIAL. COVER NEW STRUTS AND CLAMPS IN AREA WHERE STEEL IS UNCOVERED. DO SO IN ACCORD TO MANUFACTURER'S INSTRUCTIONS.
- B. Drawing Add to Key note 9; SUPPORT CONDUIT EXTENSION IN A MANNER SIMILAR TO THAT DESCRIBED IN PARAGRAPH A ABOVE.

END OF ADDENDUM NO. 1. This addenda consists of one (1) type written page.

Natatorium HVAC Replacement
RiverPlex Recreation and Wellness Center