

ADDENDUM NUMBER 2

Peoria Park District  
Planning, Design and Construction Department  
1314 N. Park Road  
Peoria, Illinois 61604  
Telephone (309) 686- 3386

PROJECT TITLE:  
Natatorium HVAC Replacement  
RiverPlex Recreation and  
Wellness Center  
600 N.E. Water St.  
Peoria, Illinois 61603  
PPD Project # 19-023  
Dated Feb 23, 2021

ISSUANCE DATE: 9 March 2021

LOCATION: **RiverPlex Recreation and Wellness Center**

The proposed Contract Documents for this Work are modified as follows:

I. PROJECT MANUAL / SPECIFICATIONS/GENERAL CONDITIONS/ETC:

A. Section 051200 It is noted paragraph 2.7 A. 2. Reads "Galvanize all exterior exposed steel". There will be no painting of steel required.

B. Section 230710:

1. Paragraph 2.02.D: Add sentence. Elbow covers for Victaulic type pipe shall include molded space for coupling clamp and insulation.
2. Add paragraph 3.03.B.6 "Insulate Victaulic fittings and clamps with narrow wrappings of 1" thick fiberglass blanket insulation. Finish with a pre-molded insulation cover; specifically made for the "Victaulic" pipe.

C. Section 232113:

1. Under paragraph 2.04 the second paragraph A and following paragraphs B,C and A shall all be deleted. Add these paragraphs in their stead.  
  
"B. At Contractor's option Pipe fittings 2 " and above, shall be Victaulic PGS-300 grooved end type with type 356 and 357 fitting clamps. Reducing clamps shall not be used. Pipe size reductions shall be made per paragraph 3.02.R.3 or as noted in item 2 below.  
  
C. Pipe 2" in diameter shall utilize solvent cement connections as noted above.
2. Under paragraph 3.02.R add subparagraph: "5. Use of reducing 'tees' and 'couplings' is acceptable."

II. DRAWINGS:

Regarding the note on Drawing DH-101 which begins "PUMP DOWN AND COLLECT REFRIGERANT..." change that note to read. "EXISTING REFRIGERANT EQUIPMENT DATA Listed A TOTAL REFRIGERANT CHARGE OF APPROXIMATELY 830 LBS OF R22 ORIGINALLY. IT HAS BEEN OBSERVED THE SYSTEM MAY HAVE UP TO 1400 LBS. (LEAKAGAGE RATES ARE UNKNOWN). CONTRACTOR SHALL PUMP DOWN AND REMOVE ALL REFRIGERANT. DELIVER 100 LBS TO THE OWNER IN CANISTERS FURNISHED BY THE OWNER. THE REMAINING REFRIGERANT

Natatorium HVAC Replacement  
RiverPlex Recreation and Wellness Center

SHALL BECOME THE PROPERTY OF THE CONTRACTOR.  
REMOVE THE EXISTING CONDENSING UNIT, WHICH WEIGHS APPROXIMATELY 4200  
POUNDS AND ASSOCIATED PIPE"

END OF ADDENDUM NO. 2. This addenda consists of 2 type written pages.