

Peoria Park District
Planning, Design and Construction Department
1314 N. Park Road
Peoria, IL 61604
Telephone: (309) 686-3386

ADDENDUM NO. 01

PROJECT TITLE: Siding Repairs & Paint

ISSUANCE DATE: 08.24.23

LOCATION: Kellogg Service Building - Project# 23-020

The proposed Contract Documents for this Work are modified as follows:

I. GENERAL ITEMS / CLARIFICATIONS:

1. Paint only the exterior faces of the hollow metal door frames and jambs. Paint jambs and doors up to the door stops.
2. A solid color stain will be utilized for the project to hide and fill more of the imperfections in the dry wood siding.
3. Bid date and time has not changed – 11:00 a.m. on Tuesday, August 29, 2023.
4. Reminder that this is a prevailing wage project.
5. Sealed Bids shall be delivered to the Noble Center – Peoria Park District Administrative Office in Lakeview Park.

II. PROJECT DRAWINGS:

1. Reference Drawing Sheet A1 -
 - a. Elevation 1/A1
 1. Stain wood jamb trims and frames at both overhead doors. On the West overhead door replace 2 broken pieces of wood trims with new wood trims to match existing. 1 face trim and 1 jamb trim.
 2. Skim coat rusted holes in hollow metal door with bondo prior to painting.
 3. Locate / reference far West window. To the right of this last window full height from roof to soffit above remove and replace rotten wood siding panel with new T-111 siding to match to the nearest vertical joint (48” assumption, field measure / verify)
 - b. Elevation 2/A1
 1. Reference T-111 siding replacement note referencing to replace a 8’X10’ area at south elevation with new siding. “Add the missing leader and arrow pointing to the (red) hatched area on this South elevation.

III. PROJECT MANUAL / SPECIFICATIONS:

1. Reference Section 99300 Staining and Transparent Finishing 2.2.A.1.:
 - a. Delete Transparent and provide a Solid Stain.

END OF ADDENDUM NO. 01
This Addendum consists of 1 typed page